



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

1 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Permanent Testing				
1	MECHANICAL- BUILDINGS MATERIALS	Acid Resistance Brick	Dimension Width	IS 4860
2	MECHANICAL- BUILDINGS MATERIALS	Acid Resistance Bricks	Dimension Length	IS 4860
3	MECHANICAL- BUILDINGS MATERIALS	Acid Resistance Bricks	Dimension Thickness	IS 4860
4	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Air Content	IS:9103
5	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Compressive Strength	IS:516
6	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Flexural Strength	IS 516 : Part 1 : Sec 1
7	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Length Change/Drying Shrinkage	IS 516 : Part 6
8	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Loss of Workability	IS:9103
9	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Setting Time	IS:1199(Part 7)
10	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Slump	IS 9103
11	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Test for bleeding	IS 9103
12	MECHANICAL- BUILDINGS MATERIALS	Admixtures	Water Content	IS:9103
13	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Block (AAC)	Block Density	IS 2185 (Part 4)
14	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Block (AAC)	Block Density	IS 6441(Part 1)
15	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Block (AAC)	Compressive Strength	IS 2185 (Part 4)
16	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Block (AAC)	Dimension Width	IS 2185 (Part 3)
17	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Block (AAC)	Water absorption	IS 2185 (Part 4)
18	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Blocks (AAC)	Compressive Strength	IS 6441 (Part 5)
19	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Blocks (AAC)	Dimension Length	IS 2185 (Part 3)
20	MECHANICAL- BUILDINGS MATERIALS	Autoclave Aerated Concrete Blocks (AAC)	Dimension Thickness	IS 2185 (Part 3)
21	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Absolute viscosity	IS 1206 (Part 2)
22	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Ductility	IS 1208

This is annexure to 'Certificate of Accreditation' and does not require any signature.



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

2 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
23	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Fire point	IS 1209
24	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Flash point	IS 1209
25	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Kinematic Viscosity	IS 1206 (Part 3)
26	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Loss on heating	IS 1212
27	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Penetration	IS 1203
28	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Softening point	IS 1205
29	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Solubility in Trichloroethylene	IS 1216
30	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Specific gravity	IS 1202
31	MECHANICAL- BUILDINGS MATERIALS	Bitumen & Allied Materials ,Modified Bitumen, PMB,CRMB, NRMB	Viscosity ratio(RTFOT Residue)	IS 1206 (Part 2)
32	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Coagulation of emulsion at low temperature	IS 8887
33	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Coating Ability and Water Resistance	IS 8887
34	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Ductility	IS1208
35	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Miscibility with water	IS 8887
36	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Penetration	IS 1203
37	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Residue by Evaporation	IS 8887
38	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Residue on 600 micron IS Sieve	IS 8887
39	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Solubility in Trichloroethylene	IS 1216
40	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Stability to Mixing With Cement	IS 8887
41	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Storage Stability after 24 Hours	IS 8887
42	MECHANICAL- BUILDINGS MATERIALS	Bitumen Emulsion	Viscosity by saybolt furol viscometer	IS 3117
43	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Binder/ Bitumen Content	ASTM D 2172
44	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Binder/ Bitumen Content	IRC SP 11



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

3 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
45	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Density	ASTM D 2726
46	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Flow Value	ASTM D 6927
47	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Gradation (Sieving)	IS 2386 (Part 1)
48	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Marshal stability	ASTM D 6927
49	MECHANICAL- BUILDINGS MATERIALS	Bitumen Mix Material	Theoretical Maximum Specific Gravity	ASTM D 2041
50	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Brick, Fly ash Brick & Fly ash lime Brick, sewer brick, Acid Resistance Brick	Compressive strength	IS 3495 (Part 1)
51	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Brick, Fly ash Brick & Fly ash lime Brick, sewer brick, Acid Resistance Brick	Water absorption	IS 3495 (Part 2)
52	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Brick, Fly ash Brick & Fly ash lime Brick, Sewer Bricks	Efflorescence	IS 3495 (Part 3)
53	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Bricks	Dimension Length	IS 1077
54	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Bricks	Dimension Thickness	IS 1077
55	MECHANICAL- BUILDINGS MATERIALS	Burnt Clay Bricks	Dimension Width	IS 1077
56	MECHANICAL- BUILDINGS MATERIALS	Cement	Compressive strength (168 ± 2Hrs)	IS 4031(Part 6)
57	MECHANICAL- BUILDINGS MATERIALS	Cement	Compressive strength (672 ± 4Hrs)	IS 4031(Part 6)
58	MECHANICAL- BUILDINGS MATERIALS	Cement	Compressive strength (72 ± 1Hrs)	IS 4031(Part 6)
59	MECHANICAL- BUILDINGS MATERIALS	Cement	Consistency	IS 4031 (Part 4)
60	MECHANICAL- BUILDINGS MATERIALS	Cement	Density	IS 4031(Part 11)
61	MECHANICAL- BUILDINGS MATERIALS	Cement	Drying shrinkage	IS 4031 (Part 10)
62	MECHANICAL- BUILDINGS MATERIALS	Cement	Final Setting time	IS 4031(Part 5)
63	MECHANICAL- BUILDINGS MATERIALS	Cement	Fineness by Blaine air permeability	IS 4031(Part 2)
64	MECHANICAL- BUILDINGS MATERIALS	Cement	Initial Setting Time	IS 4031(Part 5)
65	MECHANICAL- BUILDINGS MATERIALS	Cement	Soundness By Autoclave method	IS 4031(Part 3)
66	MECHANICAL- BUILDINGS MATERIALS	Cement	Soundness By Le-Chatelier method	IS 4031(Part 3)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

4 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
67	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Dimension Length	IS 1237
68	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Dimension Thickness	IS 1237
69	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Dimension Width	IS 1237
70	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Flatness of the tiles surface	IS 1237
71	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Perpendicularity	IS 1237
72	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Straightness	IS 1237
73	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete flooring Tiles	Thickness of wearing Layer	IS 13801
74	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Water absorption	IS 1237
75	MECHANICAL- BUILDINGS MATERIALS	Cement Concrete Flooring Tiles	Wet Transverse strength	IS 1237
76	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Dimension Length	IS 13801
77	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Dimension Thickness	IS 13801
78	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Dimension Width	IS 13801
79	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Flatness of the tiles surface	IS 13801
80	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Perpendicularity	IS 13801
81	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Straightness	IS 13801
82	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Thickness of wearing layer	IS 13801
83	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Water absorption	IS 13801
84	MECHANICAL- BUILDINGS MATERIALS	Chequered Cement Concrete Tiles	Wet Transverse strength	IS 13801
85	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Surface Moisture	CPWD specification volume-1,Chapter-4,Appendix-B,Clause-4.1.1.5
86	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Surface Moisture	IS 2386(Part-3)
87	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Total Deleterious Material	IS 2386(Part-1&2)
88	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	10% Fines Value (Ton)	BS 812 (Part 111)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

5 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
89	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	10% Fines Value (Ton)	IS 2386 (Part 4)
90	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Bulk density	IS 2386(Part 3)
91	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Crushing Value	IS 2386 (Part 4)
92	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Deleterious materials Clay & Lumps	IS 2386 (Part 2)
93	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Elongation Index	IS 2386 (Part 1)
94	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Flakiness Index	IS:2386(Part 1)
95	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Impact Value	IS 2386 (Part 4)
96	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Organic Impurities	IS 2386 (Part 2)
97	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Sieve Analysis (2.36 to 125)mm	IS 2386 (Part 1)
98	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Soundness (Mg2SO4) (Na2SO4)	IS 2386 (Part-5)
99	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Specific Gravity	IS 2386 (Part 3)
100	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Water Absorption	IS 2386 (Part 3)
101	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Arris/ Chamfer (Depth)	IS 15658
102	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Arris/ Chamfer (Width)	IS 15658
103	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Aspect Ratio, (L/T)	IS15658 (Annex-B)
104	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Compressive Strength	IS 15658 (Annex-D)
105	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Dimension Length	IS 15658(Annex-B)
106	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Dimension Thickness	IS 15658 (Annex-B)
107	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Dimension Width	IS 15658 (Annex-B)
108	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Flexural strength/ Breaking load	IS 15658 (Annex-G)
109	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Plan Area, Asp	IS 15658 (Annex-B)
110	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Squareness	IS 15658



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

6 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
111	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Thickness of Wearing layer	IS 15658 (Annex-B)
112	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Visual inspection	IS 15658
113	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Water Absorption	IS 15658 (Annex-C)
114	MECHANICAL- BUILDINGS MATERIALS	Concrete Block for Paving (Paver Block)	Wearing face area, (Asw)	IS 15658 (Annex-B)
115	MECHANICAL- BUILDINGS MATERIALS	Concrete Cube & Core	Compressive strength	IS 516
116	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Bulk density	IS 2386(Part 3)
117	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Bulking of sand	IS: 2386 (Part 3)
118	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Deleterious materials Clay & Lumps	IS 2386 (Part 2)
119	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Material Finer than 75 microns	IS 2386 (Part 1)
120	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Organic Impurities	IS (2386 (Part 2)
121	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Sieve Analysis (10mm to 150 microns)	IS 2386 (Part 1)
122	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Silt Content	CPWD specifiaction volume-1,Chapter-3,Appendix-C (Clause-3.1.3.2)
123	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Soundness (Mg2SO4) (Na2SO4)	IS 2386(Part-5)
124	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Specific Gravity	IS 2386 (Part 3)
125	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Surface Moisture	CPWD specifiaction volume-1,Chapter-4,Appendix-B,Clause-4.1.1.5
126	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Surface Moisture	IS 2386 (Part-3)
127	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Total Deleterious Materials	IS 2386(Part-1&2)
128	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Water Absorption	IS 2386 (Part 3)
129	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Compressive strength	IS 1727
130	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Fineness by Blain Permeability Method	IS 1727
131	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Lime Reactivity	IS 1727
132	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Moisture Content	IS 3812 (Part1 & 2)

This is annexure to 'Certificate of Accreditation' and does not require any signature.



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

7 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
133	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Residue retained on 45 micron (Wet Sieving)	IS 1727
134	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Soundness Autoclave expansion	IS 1727
135	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Specific Gravity	IS 1727
136	MECHANICAL- BUILDINGS MATERIALS	Fly ash Bricks	Dimension Length	IS 13757
137	MECHANICAL- BUILDINGS MATERIALS	Fly ash Bricks	Dimension Thickness	IS 13757
138	MECHANICAL- BUILDINGS MATERIALS	Fly ash Bricks	Dimension Width	IS 13757
139	MECHANICAL- BUILDINGS MATERIALS	Fly ash lime Brick	Dimension Length	IS 12894
140	MECHANICAL- BUILDINGS MATERIALS	Fly ash lime Bricks	Dimension Thickness	IS 12894
141	MECHANICAL- BUILDINGS MATERIALS	Fly ash lime Bricks	Dimension Width	IS 12894
142	MECHANICAL- BUILDINGS MATERIALS	Fresh Concrete	Air Content	IS 1199 (Part-4)
143	MECHANICAL- BUILDINGS MATERIALS	Fresh Concrete	Density	IS 1199 : Part 3
144	MECHANICAL- BUILDINGS MATERIALS	Fresh Concrete	Setting Time	IS 1199 : Part 7
145	MECHANICAL- BUILDINGS MATERIALS	Fresh Concrete	Slump	IS 1199 (Part-2)
146	MECHANICAL- BUILDINGS MATERIALS	Glass Beads	Gradation	BS 6088
147	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Bulk Density	IS 13630(Part-2)
148	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Dimension (Length, Width, Thickness)	IS 15622
149	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Modulus of rupture	IS 13630(Part 6)
150	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Modulus of Rupture	IS 4457
151	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Resistance to acids and Alkalies	IS 13630(Part-7&8)
152	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Resistance to House Hold Chemical and Swimming Pool water	IS 13630(Part-7&8)
153	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Resistance to Staining	IS 13630(Part-7&8)
154	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Resistance to Thermal Shock	IS 13630(Part-5)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

8 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
155	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Scratch Hardness	IS 13630(Part 13)
156	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile, Vitreous Acid Resistance Tiles	Dimension (Length, Width, Thickness)	IS 13630 (Part 1)
157	MECHANICAL- BUILDINGS MATERIALS	Glazed Tile, Unglazed Tile, Vitrified Tile	Water Absorption	IS 13630(Part 2)
158	MECHANICAL- BUILDINGS MATERIALS	Glazed Tiles, Unglazed Tiles, Vitrified Tiles	Breaking Strength	IS 13630 (Part 6)
159	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete	Compressive Strength	IS 516 : Part 1 : Sec 1
160	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete	Drying Shrinkage	IS 516 : Part 6
161	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete	Flexural Strength	IS 516
162	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete	Flexural Strength	IS 516 : Part 1 : Sec 1
163	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Block Density	IS 2185 (Part 1)
164	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Block Density	IS 2185 (Part 2)
165	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Compressive Strength	IS 2185 (Part 1)
166	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Compressive Strength	IS 2185 (Part 2)
167	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Dimension Length	IS 2185 (Part 1)
168	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Dimension Thickness	IS 2185 (Part 1)
169	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Dimension Width	IS 2185 (Part 1)
170	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Water absorption	IS 2185 (Part 1)
171	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid Concrete Blocks	Water absorption	IS 2185 (Part 2)
172	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid light weight Concrete Blocks	Dimension Thickness	IS 2185 (Part 2)
173	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid light weight Concrete Blocks	Dimension Length	IS 2185 (Part 2)
174	MECHANICAL- BUILDINGS MATERIALS	Hollow & Solid light weight Concrete Blocks	Dimension Width	IS 2185 (Part 2)
175	MECHANICAL- BUILDINGS MATERIALS	Mastic Asphalt	Hardness Test	IS 1195
176	MECHANICAL- BUILDINGS MATERIALS	Micri Silica	Moisture Content	IS 15388



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

9 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
177	MECHANICAL- BUILDINGS MATERIALS	Micro Silica	Compressive Strength	IS 1727
178	MECHANICAL- BUILDINGS MATERIALS	Micro Silica	Material retained on 45micron IS sieve	IS 1727
179	MECHANICAL- BUILDINGS MATERIALS	Precast Concrete Kerbs, Channels,Edging,Quadrants and Other Associated Fittings	Compressive Strength	IS 516(Part-4)
180	MECHANICAL- BUILDINGS MATERIALS	Precast Concrete Kerbs, Channels,Edging,Quadrants and Other Associated Fittings	Dimensions	IS 5758
181	MECHANICAL- BUILDINGS MATERIALS	Precast Concrete Kerbs, Channels,Edging,Quadrants and Other Associated Fittings	Water Absorption	IS 5758
182	MECHANICAL- BUILDINGS MATERIALS	Preformed foam cellular concrete blocks	Dimension Length	IS 2185 (Part 4)
183	MECHANICAL- BUILDINGS MATERIALS	Preformed foam cellular concrete blocks	Dimension Thickness	IS 2185 (Part 4)
184	MECHANICAL- BUILDINGS MATERIALS	Preformed foam cellular concrete blocks	Dimension Width	IS 2185 (Part 4)
185	MECHANICAL- BUILDINGS MATERIALS	Sewer Bricks	Dimension Length	IS 4885
186	MECHANICAL- BUILDINGS MATERIALS	Sewer Bricks	Dimension Thickness	IS 4885
187	MECHANICAL- BUILDINGS MATERIALS	Sewer Bricks	Dimension Width	IS 4885
188	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Breaking Strength	IS 4457
189	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Dimension (Length, Width, Thickness)	IS 4457
190	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Resistance to Acids and Alkalies	IS 4457
191	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Resistance to Concentrated Nitric Acid and Sulphuric Acid	IS 4457
192	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Resistance to Household Chemical and swimming pool water	IS 4457
193	MECHANICAL- BUILDINGS MATERIALS	Vitreous Acid Resistance Tiles	Water Absorption	IS 4457
194	MECHANICAL- SOIL AND ROCK	Bentonite	Density	IS: 2911 (Part 1, Section 2)
195	MECHANICAL- SOIL AND ROCK	Bentonite	Fineness	IS 6186
196	MECHANICAL- SOIL AND ROCK	Bentonite	Free Swell Index	IS 2720 (Part 40)
197	MECHANICAL- SOIL AND ROCK	Bentonite	Gel Formation Index	IS 6186
198	MECHANICAL- SOIL AND ROCK	Bentonite	Liquid Limit	IS 2720 (Part 5)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

10 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
199	MECHANICAL- SOIL AND ROCK	Bentonite	Loss on Ignition	IS 6186
200	MECHANICAL- SOIL AND ROCK	Bentonite	Marsh Viscosity	ASTM D 6910
201	MECHANICAL- SOIL AND ROCK	Bentonite	Matter Soluble In Water	IS 6186
202	MECHANICAL- SOIL AND ROCK	Bentonite	Moisture	IS 6186
203	MECHANICAL- SOIL AND ROCK	Bentonite	Sand Content	IS 6186
204	MECHANICAL- SOIL AND ROCK	Natural Stone	Apparent Specific Gravity	IS 1124
205	MECHANICAL- SOIL AND ROCK	Natural Stone	Compressive Strength	IS 1121 (Part 1)
206	MECHANICAL- SOIL AND ROCK	Natural Stone	Durability	IS 1126
207	MECHANICAL- SOIL AND ROCK	Natural Stone	Moisture Content	IS 1124
208	MECHANICAL- SOIL AND ROCK	Natural Stone	Porosity (True and Apparent)	IS 1124
209	MECHANICAL- SOIL AND ROCK	Natural Stone	Resistance to wear	IS 1706
210	MECHANICAL- SOIL AND ROCK	Natural Stone	Scratch Hardness	IS 13630 (Part 13)
211	MECHANICAL- SOIL AND ROCK	Natural Stone	Specific Gravity	IS 1124
212	MECHANICAL- SOIL AND ROCK	Natural Stone	Tensile strength	IS 1121 (Part 3)
213	MECHANICAL- SOIL AND ROCK	Natural Stone	Transverse Strength	IS 1121 (Part 2)
214	MECHANICAL- SOIL AND ROCK	Natural Stone	Water absorption	IS 1124
215	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Free Swell Index	IS: 2720 (Part 40)
216	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Grain size analysis (Sieve Analysis)	IS 2720 (Part 4)
217	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Grain size analysis (Sieve Analysis)	IS 2720 (Part 4)
218	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	CBR	IS 2720 (Part 16)
219	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Heavy Compaction (MDD)	IS 2720 (Part 8)
220	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Heavy Compaction (OMC)	IS 2720 (Part 7)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRATEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

11 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
221	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Light Compaction (MDD)	IS 2720 (Part 7)
222	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Light Compaction (OMC)	IS 2720 (Part 7)
223	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Liquid Limit	IS 2720 (Part 5)
224	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Moisture Content	IS: 2720 (Part 2)
225	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Plastic limit	IS 2720 (Part 5)
226	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Shrinkage Limit	IS 2720 (Part 6)
227	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Specific Gravity	IS 2720 (Part 3/ Sec-2)



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

INFRA TEST INVESTIGATION AND RESEARCH CENTRE PRIVATE LIMITED,
KHASRA NO.257, VILLAGE: SHERPUR NAGAR NIGAM, ROORKEE,
UTTARAKHAND, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-13666

Page No

12 of 12

Validity

05/07/2024 to 10/05/2026

Last Amended on

-

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Site Testing				
1	MECHANICAL- SOIL AND ROCK	Soil and Rock	ELECTRICAL RESISTIVITY TEST	IS:15736
2	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Field density by Core cutting method	IS 2720 (Part 29)
3	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Field density by Sand replacement method	IS 2720 (Part 28)
4	MECHANICAL- SOIL AND ROCK	Soil Earthwork, Sub grade, Sub Base, Non Bituminous,GSB, WBM, WMM	Standard Penetration	IS 2131
5	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Material-Reinforced Concrete Structure	Half Cell Potential	ASTM C 876
6	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structure/Cement concrete/ Structural Members	Carbonation Test	BS EN 14630
7	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structure/Cement concrete/ Structural Members	Carbonation Test	IS 516 (Part 5/Sec 3)
8	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structure/Cement concrete/ Structural Members	Rebound Hammer Test	IS 516 : Part 5 : Sec 4
9	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Reinforced Concrete Structure/Cement concrete/ Structural Members	Ultra Sonic Pulse Velocity	IS 516 (Part 5/Sec 1)